

Item Part # Description

1. 1127473R SMART3™ Solenoid Cover - Refurb

2. 1705791 Solenoid Cover Gasket


3. 1704367 Hex Flange Cap Screw - #10 x 3/4"

STEP 1: Disconnect power to trailer. Remove existing cover from the receiver bracket by removing eight screws with a 5/16" socket. Separate cover from bracket and gasket. DO NOT disconnect wire at this point.

NOTE: Minimal force may be needed to break existing seal of gasket to box.

STEP 2: Label each connection with tape to easily identify for reconnecting wires in Step 5.

HINT: Take photograph of existing wiring to reference later when reconnecting.



PO BOX 713 • 2309 SHUR-LOK STREET YANKTON, SOUTH DAKOTA 57078-0713 PH. 1-800-474-8756 • FAX 605-665-0501



SHUR-CO® HELP LIN CALL: 1-866-748-743 www.shurco.con

- **STEP 3:** Disconnect nine wires freeing cover from solenoid and bracket.
- **STEP 4:** Remove old gasket and clean all dirt and debris from receiver bracket. Place new gasket **②** on bracket.
- STEP 5: Connect wires from new SMART3™ cover **①** to solenoid. Use wiring diagram below for reference.
- **STEP 6:** Reconnect power to trailer and verify correct operation.
- **STEP 7:** Replace solenoid and secure with new cap screws **3**.
- STEP 8: Use packaging from replacement receiver to box old receiver. Call Shur-Co® customer service help-line at 1-866-748-7435 to obtain an RMA number and arrange for UPS pick up.

NOTE: RMA's are required for all return shipments.

